

Sealed bid #25

(Bid deadline April 2nd at 4:30 PM)

All work to be completed before July 1st.

Phase #1 Maintenance shop/warehouse

- Building dimensions – 55'width x 63'length x 14'- 4" height.
- Remove all steel and insulation from exterior walls and roof.
- Remove 3 overhead doors.
- Frame in center overhead door opening.
- Remove and frame in two windows.
- Remove and install new treated Tung and Groove skirt boards around all perimeter of building.
- Install two new 12' x 12' insulated overhead doors and operators, Include 4 remotes to operate both doors.
- Install new 28 gauge steel on all exterior walls and roof. Flash to adjoining building as needed.
- Install gutter and 4 drops.
- Install new Insulated walk-in door.

Please contact Scot Wetjen with any questions: 319-981-6516

Note: Please mark envelopes as "sealed bid #25" and either mail to, or drop off at the Iowa County Auditor Office at: 970 Court Avenue, Marengo, IA. 52301